



INNAMINCKA
PETROLEUM
ACN 101 313 777

Office 1 - Ground Floor
924 Gympie Road
CHERMSIDE QLD 4032

PO Box 2378
CHERMSIDE QLD 4032
Telephone: (07) 3359 8988
Facsimile: (07) 3359 8985
www.innapet.com.au

ANNOUNCEMENT TO ASX

Date: 14 April 08

To: Australian Securities Exchange
Companies Announcement Office
Electronic Lodgment System

Dear Sir

Drilling Report - Flax 7 ST1

Innamincka Petroleum advises that as of 06:00 hours this morning, the Flax 7 ST1 development well was at a depth of 2609 m having sidetracked Flax 7 from 2171m. Current operation is drilling ahead 8 ½" hole.

The well is prognosed to reach a total depth of 2830 metres over an operational period of 22 days.

Daily updates of drilling progress are posted also on the company website www.innapet.com.au

Participants in the project are:

Innamincka (operator)	75%
SCGAU	25%

Yours sincerely

Innamincka Petroleum Limited

Leni Stanley
Company Secretary



INNAMINCKA
PETROLEUM

FLAX 7 / ST1 TIME DEPTH CURVE ACTUAL VS PROGNOSED

WELL DETAILS

Rig: Ensign Rig 30
RT: 96.0 m
GL: 88.9 m
Total Depth: 2830 m (Planned)
Drill Days: 22 from spud

HOLE / CASING SIZES

311 mm (12-1/4") Surface hole to 885m
245 mm (9-5/8") Surface Casing Set @ 882 m
216 mm (8-1/2") Main Hole to XXXX m (TD)
178 mm (7") Production Casing Set @ XXXX m

LOCATION DETAILS

Well Type: Development
Permit: PRL 14
Distance: 120 km NNE of Moomba

MAJOR DATES

Well Spudded: 06:00 hrs 31 Mar 08
Reached TD: XX:XX hrs XX Apr 08
Rig Released: XX:XX hrs XX Apr 08

